

SAFE DRINKING WATER AND SANITARY CONDITION CERTIFICATE

No.

Dated:

It is certified that an inspection team headed by ...Bharadham mehar..... from **PHE** inspected the Vidyakunj International School, **SURVAY NUMBER 84/2/1 VILLAGE LONDIYA DIST SHAJAPUR, MP** on 17/03/2025... and found that the **Vidyakunj International School** has safe drinking water facilities for the students and members of staff of the institution and is maintaining the ~~hygienic sanitation condition~~ in the school building & the campus as per norms prescribed by the Central/ State/ U.T. Govt

The above is valid for a period of **One Year**


Assistant Engineer

Signature with Seal **P.H.E. Sub-Div. Shajapur**.....

Name : ...Bharadham mehar.....

Designation: **Assistant Engineer, PHE, Shajapur**

To

Vidyakunj International School

SURVAY NUMBER 84/2/1

VILLAGE LONDIYA

DIST SHAJAPUR, MP

465001


Principal

Vidyakunj International School


Director

Vidyakunj International School

DISTRICT WATER TESTING LABORATORY PUBLIC HEALTH ENGINEERING DEPARTMENT LAL GHATI-SHAJAPUR											
BLOCK-SHAJAPUR						DATE-17/03/2025					
Type Of Sample-SCHOOLWATER											
Particulars of sender-DIRECTOR VIDHYAKUNJ INTERNATIONAL SCHOOL- SHAJAPUR											
Particulars of sample- Collected/not collected by PHED											
Sample No.	Place of Collection and details of Sample				Sample No.	Place of Collection and details of Sample					
1	SHAJAPUR-VIDHYAKUNJ INTERNATIONAL SCHOOL										
	Parameter	Units	As per BIS 10500:2012 for Drinking Water								
			Requirement (desirable limit)	Permissible limit in the absence of alternate source	Sample 1						
PHYSICAL TEST											
1*	Temperature	°C			25						
2*	Turbidity	NTU	1.0	5.0	0.1						
3*	Colour	Hazen	5	15	5.0						
4*	Odour		Agreeable	Disagreeable	Agreeable						
5*	TASTE		Agreeable	Disagreeable	Agreeable						
CHEMICAL TEST											
6*	pH	pH scale	6.5 to 8.5	No Relaxation	7.2						
7*	Total Hardness as CaCO ₃	Mg/l	200	600	48.5						
8*	Calcium as Ca	Mg/l	75	200	14.0						
9*	Magnesium as Mg	Mg/l	30	100	3.3						
10*	Total alkalinity as CaCO ₃	Mg/l	200	600	46.1						
11*	Chloride as Cl	Mg/l	250	1000	18.9						
12	Nitrate as NO ₃	Mg/l	45	45	4.0						
13*	Total Dissolved Solids	Mg/l	500	2000	74.0						
14	Iron	Mg/l	1.0	1.0	0.1						
15	Sulphate as SO ₄	Mg/l	200	400	6.0						
16	Fluoride as F	Mg/l	1.0	1.5	0.16						
17	Magnesium as Mn	Mg/l	0.1	0.3	0.0						
18	Residual Chlorine as Cl ₂	Mg/l	0.2	1.0	0.0						
19	Total coliform	Per 100 ml	Nil	Nil	Nil						
20	Faecal coliform	Per 100 ml		Nil	Nil						

Note:- 1. This report should not be produced partly of full without approval of signatory authority for legal purposes.
2. This recommended that acceptable limit is to be implemented. Values in excess of those mentioned under "acceptable" render the water not suitable, still may be tolerated in the absence of an alternative source but up to the limits indicated under the "permissible limit in the absence of alternate source" above which the source will have to be rejected.
3. The results refer only to tested samples and parameters tested.
4. Sample will be stored for a period of 10 days from the date of issue of report.
5. This Lab does not hold any responsibility for variation in results for samples kept on hold for want of Clarification.
6. The tests marked with an * are accredited by NABL.

Chemist

Distt. water testing laboratory
P.H.E.D. Shajapur

Assistant Engineer
Sub Division P.H.E.D.
Shajapur

Principal
Radhe
Vidyakunj International School

Director
Balidan
Vidyakunj International School